

*Table: 15-4*

Typical values for demand factor g for:

	offices	switchgear installations
installations		
lighting	0.8	0.8
receptacles	0.1	0.1
air-conditioning, ventilation	1	1
heating	1	1
lifts	0.5 / 0.7	—
kitchen equipment	0.5	—
outside lighting (floodlight installations)	—	1
cranes	—	0.7
control and signalling equipment	—	0.5
data processing equipment	depending on the individual case	